

Memorandum to the City of Markham Committee of Adjustment

March 18, 2019

File: A/06/19
Address: 25 Talisman Cres, Markham
Applicant: Kevin & Anita Guidolin
Agent: Memar Architects INC (Lucy Mar Guzman)
Hearing Date: Wednesday March 27, 2019

The following comments are provided on behalf of the East Team:

The applicant is requesting relief from the following requirements of By-law 1229, R1, as amended:

a) Section 11.1:

a maximum lot coverage of 35.58 percent, whereas the By-law permits a maximum lot coverage of 35 percent;

b) Infill By-law 99-90, Section 1.2 (vi):

a maximum Net Floor Area Ratio of 48.53 percent, whereas the By-law permits a maximum Net Floor Area Ratio of 45 percent;

as they relate to a proposed residential dwelling.

The Committee of Adjustment deferred the application on February 20, 2019, due to concerns with the proposed dwelling. In response to the Committee of Adjustment's comments, the applicant submitted revised drawings on March 07, 2019 (Appendix 'B1') which show the removal and reduction of some of the previously requested variances. The applicant removed the previous variances requesting maximum front step encroachment of 5.3 ft (1.62 m) and maximum building depth of 18.64 m (61.2 ft).

The applicant is requesting relief to permit a floor area ratio of 48.53 percent, whereas the By-law permits a maximum floor area ratio of 45 percent. This is a reduction from the previous request for a floor area ratio of 54.1 percent. The variance will facilitate the construction of a two-storey detached dwelling with a floor area of approximately 317.93 m² (3,422.17 ft²), whereas the By-law permits a dwelling with a maximum floor area of 294.75 m² (3,172.66 ft²). This represents an increase of approximately 23.18 m² (249.51 ft²). While the proposed a dwelling will be larger than the existing detached dwelling developed around the 1950s, it maintains all setbacks and is generally consistent with recent infill development throughout the neighbourhood. Staff are of the opinion that the increase in floor area ratio is appropriate development. The applicant is requesting relief for a maximum lot coverage of 35.58 percent, whereas the By-law permits a maximum lot coverage of 35 percent. Staff's comments dated February 12, 2019 remain applicable.

Applicant's Stated Reason(s) for Not Complying with Zoning

According to the information provided by the applicant, the reason for not complying with Zoning is, "design restrictions".

Zoning Preliminary Review Undertaken

The applicant has completed a Zoning Preliminary Review (ZPR) to confirm the initial variances required for the proposed development. The applicant submitted revised drawings on March 07, 2019. The applicant has not conducted a Zoning Preliminary Review for the revised drawings. Consequently, it is the owner's responsibility to ensure that the application has accurately identified all the variances to the Zoning By-law required for the proposed development. If the variance request in this application contains errors, or if the need for additional variances is identified during the Building Permit review process, further variance application(s) may be required to address the non-compliance.

PUBLIC INPUT SUMMARY

No written submissions were received as of March 18, 2019. It is noted that additional information may be received after the writing of the report, and the Secretary-Treasurer will provide information on this at the meeting.


CONCLUSION

Planning Staff have reviewed the application with respect to Section 45(1) of The Planning Act, R.S.O. 1990, c. P.13, as amended, and are of the opinion that the variance request meets the four tests of the Planning Act. Staff recommend that the Committee consider public input in reaching a decision.

The onus is ultimately on the applicant to demonstrate why they should be granted relief from the requirements of the zoning by-law, and how they satisfy the tests of the Planning Act required for the granting of minor variances.

Please see Appendix "A" for conditions to be attached to any approval of this application.

PREPARED BY:



Aqsa Malik, Planner, Zoning and Special Projects

REVIEWED BY:



Stacia Muradali, Senior Planner, East District
File Path: Amanda\File\ 18 254768 \Documents\District Team Comments Memo

Appendices

Appendix A1 – Conditions

Appendix B1 – Plans


Appendix C1 – Previous Staff Report (January 15, 2019 & November 21, 2018)


APPENDIX "A1"

CONDITIONS TO BE ATTACHED TO ANY APPROVAL OF FILE A/06/19

1. That the rear covered deck remain unenclosed;
2. The variances apply only to the proposed development as long as it remains;
3. That the variances apply only to the subject development, in substantial conformity with the plan(s) attached as 'Appendix B1' to this Staff Report and received by the City of Markham on *March 07, 2019*, and that the Secretary-Treasurer receive written confirmation from the Director of Planning and Urban Design or designate that this condition has been fulfilled to his or her satisfaction;
4. Submission of a Tree Assessment and Preservation Plan, prepared by a qualified arborist in accordance with the City's Streetscape Manual (2009), as amended, to be reviewed and approved by the City, and that the Secretary-Treasurer receive written confirmation from Tree Preservation Technician or Director of Operations that this condition has been fulfilled to his/her satisfaction, and that any detailed Siting, Lot Grading and Servicing Plan required as a condition of approval reflects the Tree Assessment and Preservation Plan;
5. That prior to the commencement of construction or demolition, tree protection be erected and maintained around all trees on site in accordance with the City's Streetscape Manual, including street trees, in accordance with the City's Streetscape Manual (2009) as amended, and inspected by City Staff to the satisfaction of the Tree Preservation Technician or Director of Operations;
6. That tree replacements be provided and/or tree replacement fees be paid to the City if required in accordance with the Tree Assessment and Preservation Plan, and that the Secretary-Treasurer receive written confirmation that this condition has been fulfilled to the satisfaction of the Tree Preservation Technician or Director of Operations.



CONDITIONS PREPARED BY:


Aqsa Malik, Planner, Zoning and Special Projects



NEW HOUSE

LOT AREA: 696.85 m ²						
NET LOT AREA: 655 m ²		LOT COVERAGE: 225.44m ² (35.58%)				
NFA	FIRST FLOOR AREA NOT INCLUDING PORCH	SECOND FLOOR AREA	BASEMENT	GARAGE	TOTAL NFA NOT INCLUDING BSMT	NFAR %
TOTAL	135.41 m ²	133.86 m ²	135.41 m ²	48.66 m ²	317.93 m ²	48.53%




ALL DRAWINGS AND DOCUMENTS ARE PRELIMINARY (P.D.T.)
 APPROVED BY THE CITY AND MUST NOT BE USED FOR ANY
 CONSTRUCTION BEFORE THE ISSUANCE OF BUILDING
 PERMIT. CONTRACTORS MUST VERIFY ALL
 DIMENSIONS AND LOCATIONS OF ALL UTILITIES
 INCLUDING STRUCTURAL AND MECHANICAL PRIOR TO
 COMMENCEMENT OF WORK AND REPORT ANY DISCREPANCIES
 IMMEDIATELY.
 DESIGN DRAWINGS & SPECIFICATIONS ARE THE PROPERTY OF
 MEMAR ARCHITECTS INC. AND MUST NOT BE REPRODUCED OR
 USED FOR ANY OTHER PROJECT WITHOUT THE WRITTEN PERMISSION
 OF MEMAR ARCHITECTS INC.

DATE:	ISSUED FOR:

DRAWING TITLE:
AREA CALCULATIONS
PROJECT TITLE/ADDRESS:
25 TALISMAN CRES, MARKHAM

DRAWN BY:
L.M.
CHECKED BY:
S.T.


SCALE:
1:200, 1:50, 1:250
LAST MODIFIED ON:
Monday, March 18, 2019





"Memar Architects Inc."
 2323 Yonge St. Unit 503
 Toronto, ON, M4P 2C9
 T: 416-575-4448



A.02







THIS DRAWING IS THE PROPERTY OF MEMAR ARCHITECTS INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF MEMAR ARCHITECTS INC.


DATE	ISSUED FOR

DRAWING TITLE
FN SECOND FL
PROJECT TITLE/ADDRESS
23 TALIMAN CREB, MARKHAM

DESIGNED BY	CHECKED BY
L.A.	S.T.


SCALE
1:100
LAST MODIFIED ON
Monday, March 18, 2019

MEMAR
ARCHITECTS
Memar Architects Inc.
2323 Yonge Street 503
Toronto, ON, M4P 2C9
T: 416-575-4445




A.06

[illegible]



<p>THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN ARE THE PROPERTY OF MEMAR ASSOCIATES INC. AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF MEMAR ASSOCIATES INC. ANY VIOLATION OF THIS NOTICE SHALL BE SUBJECT TO LEGAL ACTION.</p>	
DATE	ISSUED FOR
<p>DRAWING TITLE</p> <p>NORTH ELEVATION</p> <p>PROJECT INFORMATION</p> <p>23 TUDORHILL CIRCLE, MARKHAM</p>	
<p>DRAWING BY</p> <p>L.M.</p> <p>CHECKED BY</p> <p>S.T.</p>	
<p>SCALE</p> <p>1:100</p> <p>LAST MODIFIED ON</p> <p>February / March 14, 2019</p>	
<p>MEMAR ASSOCIATES</p> <p>"Memar Architects Inc."</p> <p>2333 Yonge Street, Suite 303</p> <p>Toronto, ON, M4P 2C9</p> <p>T: 416-572-4445</p>	
<p>REGISTERED ARCHITECTS</p> <p>MEMAR ASSOCIATES INC.</p> <p>2333 YONGE STREET, SUITE 303</p> <p>TORONTO, ONTARIO M4P 2C9</p> <p>REGISTERED ARCHITECTS</p>	
<p>A.08</p>	



<small>THIS DRAWING AND ITS CONTENTS ARE THE PROPERTY OF THE ARCHITECT AND ARE NOT TO BE REPRODUCED OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT. THE ARCHITECT ASSUMES NO LIABILITY FOR ANY DAMAGE OR LOSS OF ANY KIND, INCLUDING BUT NOT LIMITED TO, CONSEQUENTIAL DAMAGES, ARISING OUT OF THE USE OF THIS DRAWING. THE ARCHITECT'S RESPONSIBILITY IS LIMITED TO THE DESIGN AND CONSTRUCTION OF THE PROJECT AS SHOWN ON THIS DRAWING. THE ARCHITECT DOES NOT WARRANT THE ACCURACY OF ANY INFORMATION PROVIDED BY OTHERS. THE ARCHITECT'S SERVICES ARE LIMITED TO THE DESIGN AND CONSTRUCTION OF THE PROJECT AS SHOWN ON THIS DRAWING. THE ARCHITECT DOES NOT WARRANT THE ACCURACY OF ANY INFORMATION PROVIDED BY OTHERS.</small>	
DATE	ISSUED FOR
DRAWING TITLE WEST ELEVATION	
PROJECT INFORMATION 25 TAILSMAN CRES. MARKHAM	
DRAWN BY L.M.	SCALE 1:100
CHECK BY S.L.	LAST MODIFIED ON Monday, March 18, 2019
MEMAR ARCHITECTS "MARKHAM ARCHITECTS INC." 2133 TORONTO AVE. SUITE 203 MARKHAM, ONTARIO L3R 9V7 T: 416-213-3448	
ONTARIO ASSOCIATION OF ARCHITECTS 2023-11-11 1-800-387-3673	
A.09	

Memorandum to the City of Markham Committee of Adjustment

February 12, 2019

File: A/06/19
Address: 25 Talisman Cres, Markham
Applicant: Kevin & Anita Guidolin
Agent: Memar Architects INC (Lucy Mar Guzman)
Hearing Date: Wednesday February 20, 2019

The following comments are provided on behalf of the East Team:

The applicant is requesting relief from the following requirements of By-law 1229, R1, as amended:

- a) **Infill By-law 99-90, Section 1.2 (iii):**
a maximum building depth of 18.64 metres, whereas the By-law permits a maximum building depth of 16.80 metres;
- b) **Section 11.2 (c) (i):**
a maximum front step encroachment of 5.3 feet into the minimum front yard setback, whereas the By-law permits a maximum 18 inch encroachment for steps into any required yard;
- c) **Section 11.1:**
a maximum lot coverage of 36.7 percent, whereas the By-law permits a maximum lot coverage of 35 percent;
- d) **Infill By-law 99-90, Section 1.2 (vi):**
a maximum Net Floor Area Ratio of 54.1 percent, whereas the By-law permits a maximum Net Floor Area Ratio of 45 percent;

as they relate to a proposed residential dwelling.

BACKGROUND

Property Description

The 696.85 m² (7,500.83 ft²) subject property is located on the south side of Talisman Crescent, north of Ramona Boulevard and east of Main Street Markham North. The property is located within a residential neighbourhood comprised of a mix of one and two-storey detached dwellings. There is an existing one-storey detached 100.40 m² (1,080.7 ft²) dwelling on the property, which according to assessment records was constructed in 1956. Mature vegetation exists across the front and rear of the property.

Proposal

The applicant is proposing to construct a new two-storey detached 351.21 m² (3,780.4 ft²) dwelling with a finished basement, rear covered deck and rear walkout.

Official Plan and Zoning

Official Plan 2014 (partially approved on Nov 24/17, and further updated on April 9/18)

The subject property is designated "Residential – Low Rise", which provides for low rise housing forms including single detached dwellings. Infill development is required to meet the general intent of the 2014 Official Plan with respect to height, massing and setbacks to ensure that the

development is appropriate for the site and also generally consistent with the zoning requirements for adjacent properties and properties along the same street. Regard must also be had for retention of existing trees and vegetation, as well as the width of proposed garages and driveways. Planning staff have had regard for the infill development criteria in the preparation of the comments provided below.

Zoning By-Law 1229

The subject property is zoned R1 'Residential' in By-law 1229, as amended, which permits a single detached dwelling. The proposed development does not comply with the by-law with respect to maximum front step encroachment and maximum lot coverage.

Residential Infill Zoning By-law 99-90

The subject property is also subject to the Residential Infill Zoning By-law 99-90. The intent of this By-law is to ensure the built form of new residential construction will maintain the character of existing neighbourhoods. It specifies development standards for building depth, garage projection, garage width, net floor area ratio, height, yard setbacks and number of storeys. The proposed development does not comply with the infill By-law requirements with respect to maximum building depth and maximum net floor area ratio.

Applicant's Stated Reason(s) for Not Complying with Zoning

According to the information provided by the applicant, the reason for not complying with Zoning is, "*design restriction*".

Zoning Preliminary Review (ZPR) Undertaken

The owner has completed a Zoning Preliminary Review (ZPR) on November 28, 2019 to confirm the variances required for the proposed development.

COMMENTS

The Planning Act states that four tests must be met in order for a variance to be granted by the Committee of Adjustment:

- a) The variance must be minor in nature;
- b) The variance must be desirable, in the opinion of the Committee of Adjustment, for the appropriate development or use of land, building or structure;
- c) The general intent and purpose of the Zoning By-law must be maintained;
- d) The general intent and purpose of the Official Plan must be maintained.

Increase in Maximum Building Depth

The applicant is requesting relief to permit a maximum building depth of 18.64 m (61.2 ft), whereas the By-law permits a maximum building depth of 16.8 m (55.12 ft). This represents an increase of approximately 1.84 m (6.04 ft).

Building depth is measured based on the shortest distance between two lines, both parallel to the front lot line, one passing through the point on the dwelling which is the nearest and the other through the point on the dwelling which is the farthest from the front lot line.

The proposed dwelling includes a front covered porch and a garage projection which add approximately 1.25 m (4.1 ft) to the overall depth of the building, which Staff are of the opinion is minor in nature.

The proposal also includes a rear unenclosed covered one-storey deck which adds approximately 3.35 m (11 ft) to the overall depth of the building. The main building however has a depth of approximately 14.04 m (46.06 ft) which complies with the by-law requirement.

Given that the rear covered deck and front covered porch are both unenclosed, one-storey, and maintain adequate separation from neighbouring properties, and that the main building complies with the maximum building depth requirement, Staff are of the opinion that the variance request is appropriate for the development.

Increase in Maximum Front Step Encroachment

The applicant is requesting a maximum front step encroachment of 5.3 ft (1.62 m) into the front yard, whereas the By-law permits a maximum front step encroachment of 1.5 ft (0.46 m). This represents a difference of approximately 3.8 ft (1.12 m). Six steps are proposed between the first floor elevation and grade at the front of the house. Staff are of the opinion that the requested variance will not impact the street.

Increase in Maximum Lot Coverage

The applicant is requesting relief for a maximum lot coverage of 36.7 percent, whereas the By-law permits a maximum lot coverage of 35 percent. Even though there have been no other variance requests to increase the maximum lot coverage on the street, the increase is minor in nature and still maintains sufficient amenity and green space and setbacks from the property lines.

Increase in Maximum Floor Area Ratio

The applicant is requesting relief to permit a floor area ratio of 54.1 percent, whereas the By-law permits a maximum floor area ratio of 45 percent. The variance will facilitate the construction of a two-storey detached dwelling with a floor area of 351.21 m² (3,780.4 ft²), whereas the By-law permits a dwelling with a maximum floor area of 294.75 m² (3,172.66 ft²). This represents an increase of approximately 56.64 m² (607.73 ft²).

Floor Area Ratio is a measure of the interior square footage of the dwelling as a percentage of the net lot area. It is not a definitive measure of the mass of the dwelling, since it does not include "open to below" areas that may exist within the dwelling (e.g. two-storey foyers, atriums and/or stairs). In addition to the space associated with the stairs, there is an approximately 6.61 m² (71.15 ft²) open to below area on the second floor above the foyer which is excluded from the gross floor area calculation under the by-law.

The subject property is located within a residential area that consists of predominantly modest sized one-storey detached dwellings. The requested variance for maximum floor area ratio will facilitate the development of a dwelling that is larger than existing dwellings originally developed in the 1950s. There is only one other property on the street (19 Talisman) that has received a variance for maximum floor area ratio of 46.79 percent. Staff have discussed concerns over the floor area ratio variance with the applicant and to date revised plans and an amended variance application have not been received.

PUBLIC INPUT SUMMARY

No written submissions were received as of February 12, 2019. It is noted that additional information may be received after the writing of the report, and the Secretary-Treasurer will provide information on this at the meeting.

CONCLUSION

Planning Staff have reviewed the application with respect to Section 45(1) of The Planning Act, R.S.O. 1990, c. P.13, as amended, and are of the opinion that the variance request for maximum building depth, maximum front step encroachment and maximum lot coverage meets the four tests of the Planning Act. However, Staff are of the opinion that the variance request for maximum floor area ratio is not minor in nature. Staff recommend that the Committee consider public input in reaching a decision.

The onus is ultimately on the applicant to demonstrate why they should be granted relief from the requirements of the zoning by-law, and how they satisfy the tests of the Planning Act required for the granting of minor variances.


Please see Appendix "A" for conditions to be attached to any approval of this application

PREPARED BY:



Aqsa Malik, Planner, Zoning and Special Projects

REVIEWED BY:



Stacia Muradali, Senior Planner, East District


File Path: Amanda\Files\19 110645 \Documents\District Team Comments Memo

APPENDIX "A"


CONDITIONS TO BE ATTACHED TO ANY APPROVAL OF FILE A/06/19

1. That the rear covered deck remain unenclosed;
2. The variances apply only to the proposed development as long as it remains;
3. That the variances apply only to the subject development, in substantial conformity with the plan(s) attached as 'Appendix B' to this Staff Report and received by the City of Markham on *January 22, 2019*, and that the Secretary-Treasurer receive written confirmation from the Director of Planning and Urban Design or designate that this condition has been fulfilled to his or her satisfaction;
4. Submission of a Tree Assessment and Preservation Plan, prepared by a qualified arborist in accordance with the City's Streetscape Manual (2009), as amended, to be reviewed and approved by the City, and that the Secretary-Treasurer receive written confirmation from Tree Preservation Technician or Director of Operations that this condition has been fulfilled to his/her satisfaction, and that any detailed Siting, Lot Grading and Servicing Plan required as a condition of approval reflects the Tree Assessment and Preservation Plan;
5. That prior to the commencement of construction or demolition, tree protection be erected and maintained around all trees on site in accordance with the City's Streetscape Manual, including street trees, in accordance with the City's Streetscape Manual (2009) as amended, and inspected by City Staff to the satisfaction of the Tree Preservation Technician or Director of Operations;
6. That tree replacements be provided and/or tree replacement fees be paid to the City if required in accordance with the Tree Assessment and Preservation Plan, and that the Secretary-Treasurer receive written confirmation that this condition has been fulfilled to the satisfaction of the Tree Preservation Technician or Director of Operations.

CONDITIONS PREPARED BY:



Aqsa Malik, Planner, Zoning and Special Projects



TALISMAN CRESCENT
(By Registered Plan 4877)

REGISTERED PLAN 4877
CITY OF MARKHAM
Regional Municipality of York

SCALE 1:100

GTA SURVEYING INC.
© COPYRIGHT 2018

METRIC
DISTANCES SHOWN ON THIS PLAN ARE IN METERS AND CAN BE CONVERTED TO FEET BY DIVIDING BY 0.3048.

BEARING NOTE
BEARINGS ARE GIVEN IN DEGREES AND ARE REFERRED TO THE SOUTH LINE OF TALISMAN CRESCENT, BEARING A BEARING OF 89°14'12" ACCORDING TO REGISTERED PLAN 4877.

ELEVATION NOTE
ELEVATIONS ARE GIVEN IN METERS AND ARE REFERRED TO THE MEAN SEA LEVEL. ELEVATIONS ARE GIVEN TO THE TOP OF THE FINISHED ELEVATION OF 200.00 M MSL.

LEGEND

- CONCRETE
- BRICK
- WOOD
- METAL
- PLASTER
- ROOF
- FLOOR
- WALL
- CEILING
- DOOR
- WINDOW
- PORCH
- DRIVEWAY
- GARAGE
- PATIO
- DECK
- FENCE
- GROUND
- TOP OF POST ELEVATION

ASSOCIATION OF CHURCHES
LAND SURVEYORS
PLANNING AND DESIGN
20060871

SURVEYOR'S CERTIFICATE
I, THE SURVEYOR, HAVE BEEN DULY SWORN AND IN ACCORDANCE WITH THE SURVEY ACT, I HAVE CAUSED THE SURVEY TO BE MADE AND THE RESULTS TO BE SHOWN ON THIS PLAN.

PART 2 - SURVEY REPORT
1. THE SURVEY WAS PREPARED FOR THE PURPOSE OF THE SURVEY ACT, AND THE RESULTS OF THE SURVEY ARE SHOWN ON THIS PLAN.


GTA
Greater Toronto Airports Authority
SURVEYING INC.
7000 Sheppard Ave. East, Unit 13, Toronto, ON M1S 1S2
Tel: (416) 497-4372
E-MAIL: gta@gtasurveying.ca

DATE: 2018-11-20
BY: [Signature]

CITY OF MARKHAM
RECEIVED
JAN 22 2019
COMMITTEE OF ADJUSTMENT

REGISTERED



Lot Dimension: 18.29width x 38.10depth
 Lot Area: 696.85m²



<p>MEMORANDUM</p> <p>Yanna Architects Inc. 2213 Kings Street SE Victoria, BC V8W 2C4 Tel: 416-575-4443</p>		<p>A.01</p>
<p>SCALE:</p> <p>1:150 1:100</p> <p>1:100 1:50</p> <p>1:100 1:50</p>	<p>DATE:</p> <p>1/10/2017</p>	<p>PROJECT:</p> <p>25 TALISMAN CRESCENT, VICTORIA</p>
<p>DESIGNED BY:</p> <p>YANNA ARCHITECTS INC.</p>	<p>CHECKED BY:</p> <p>YANNA ARCHITECTS INC.</p>	<p>DATE:</p> <p>1/10/2017</p>
<p>SITE PLAN</p>		
<p>25 TALISMAN CRESCENT, VICTORIA</p>		

NEW HOUSE

LOT AREA: 696.85 m ²						
NET LOT AREA: 655 m ²			LOT COVERAGE: 243.46 m ² (36.70%)			
GFA	FIRST FLOOR AREA NOT INCLUDING PORCH	SECOND FLOOR AREA	BASEMENT	GARAGE	TOTAL GFA NOT INCLUDING BSMT	%
TOTAL	147.56 m ²	147.13 m ²	147.56 m ²	56.52 m ²	351.21 m ²	54.1%



ALL DIMENSIONS AND COORDINATES ARE FOR INFORMATION ONLY.
THEY DO NOT REPRESENT A GUARANTEE OF ACCURACY OR A
WARRANTY OF ANY KIND. THE USER SHALL BE RESPONSIBLE FOR
VERIFYING THE ACCURACY OF THE INFORMATION PROVIDED.
THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY
PERMITS AND APPROVALS FROM THE APPROPRIATE AUTHORITIES.
THE USER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY
INSURANCE COVERAGE FOR THE PROJECT.

DATE	ISSUED FOR


DRAWING TITLE
AREA CALCULATIONS
PROJECT INFORMATION
25 TALISMAN CREW, MARKHAM


DRAWING SET
L.A.I.
ENCL. 17
S.S.


SCALE
1:200, 1:50, 1:250
1:100, 1:50, 1:250
1:100, 1:50, 1:250


MEMOR
Memor Architect Inc. 2323 Yonge Street 503 Toronto, ON M4P 2C7 T: 416-571-4415


A.02














DATE		ISSUED FOR		DRAWING TITLE		SCALE		MEMAR ARCHITECT PC 2011 Tropic Street Tampa, FL 33601 7416-574466		A.11	
10/10/2011		FOR PERMIT		EAST ELEVATION		1:100		MEMAR ARCHITECT PC 2011 Tropic Street Tampa, FL 33601 7416-574466			
10/10/2011		FOR PERMIT		PROJECT TITLE/DATE		L.A.I.		L.A.I.			
10/10/2011		FOR PERMIT		25 FAIRMAN CIRCLE, MATHAN		C.R.B.		C.R.B.			
10/10/2011		FOR PERMIT				5.1		5.1			

